

Initial studies on a collimator system for Linac4

J. L. Fernandez-Hernando

STFC/ASTeC Daresbury Lab



Collimation of transverse H- beam halo:

FODO cells and immediate beam dumps:


- Used in the Spallation Neutron Source (SNS).
- No need to increase quad apertures.
- more collimators needed.
- more activation.

Achromat and remote beam dumps:

- Used in European Spallation Source (ESS).
- Clean as strip particles are transported to beam dumps.
- Expensive as many beam dumps needed.

FODO cells and remote beam dump:

- Used in J-Parc.
- Stripped and un-stripped particles are transported together up to the switch magnet where the 2 beams become separated and the stripped one goes to a beam dump.
- Apertures of the magnets should e increased largely otherwise beam loss will happen.





Triplets and remote beam dump

- Option for Chinese SNS (6kW and 80MeV in the linac) (Linac4 is 5.1kW and 160MeV).
- Identical waists in both planes.
- Optics for H- is good for the protons too.

J.Y. Tang et al. / Nuclear Instruments and Methods in Physics Research A 572 (2007) 601-606





Fig. 8. Layout of CSNS/LRBT.





Beam and halo model for the simulations in FLUKA

x RMS [m]	2.36E-03
x' RMS [rad]	2.75E-04
y RMS [m]	2.57E-03
y' RMS [rad]	6.66E-04

Beam 3.5 meters after the PIMS




0.0001


1e-12

1e-14






For this kind of model 10W absorption per pulse corresponds to a radial aperture of 83.3mm; 25W to 63.2mm and 50W to 39.9mm.





A pulse made of 10E14 H- with a radial beam size of around 2.5 mm and an energy of 160MeV impacting at the same point of a tungsten absorber will suppose a maximum temperature increment of around 2264K (<Tmelt=3695K).


Most of the energy is absorbed in the first 2 cm of material.






Dose limit for radiation workers is 20 mSv during a working year

be reduced to 2.5 hours









worker could stay here for as long as 27 hours (after just 1 month of operation in the machine)






month of operation of the machine a worker can stand here for 5 hours.
















OUTLOOK

- Transverse beam halo collimation required at different phases.
- Is longitudinal collimation required?
- Shorter collimators located in different positions of the beam line will serve to avoid having absorbers too hot due to activation.
- Option with foil scrappers and modified optics? Just simple absorbers along the line?
- Study of shielding and activation once these questions been resolved.