




Remarks on RF Tests of Individual SC Cavities in SM18 Vertical Test Stands

P. Maesen

SPL Collaboration meeting, 11-12 Dec '08




Content



- SM18 Presentation
- Vertical Cryostat
- Vacuum connection & leak detection
- Cool down & Warm-up
- $Q(E_{acc})$ measurement
- Discussion...





SM18 Presentation



- Test Stand for SC cavities for LEP, LHC, SOLEIL and R&D
 - Consists of :
 - 4 vertical cryostats 4.5 Kelvin
 - 2 cryostats (depth 4 m), 2 cryostats (depth 2.5 m)
 - Fed by 200 W RF amplifiers 352 or 400MHz
 - One amplifier 700-800MHz just ordered
 - He connections : lHe inlet, gas outlet and warm recovery line
 - Aging temperature probes



Vertical Cryostat




The picture shows a SOLEIL cavity in its He tank for revalidation:

- Mobile concrete bunker
- Area under RP control
- Cavity validation in vertical cryostat by measurement of $Q(E_{acc})$.
- E- emission monitoring
- Possible He processing
- Magnet shielding to be done



Vacuum connection & leak detection




Dedicated state-of-the-art processing and assembly techniques & procedures for sc cavities:

- Connections under laminar flux
- Low speed oil free vacuum pumping system
- He leak detectors
- Personnel: 2 CERN staff + 1 FSU in charge of SC cavity test infrastructure





Cool down & Warm up



- Cryo operation becomes difficult with aging ABB control interface and aging instrumentation...
- And
 - We share the He distribution with the LHC magnet test stand (2000 elements in machine) !
 - Since spring 2007 the SM18 cryo-plant capacity went down to 22 g/sec
 - Old RF transfer line consumes already 8 g/sec...
 - Very limited cryogen availability these last 2 years for SC tests




Q(Eacc) measurement





Discussion



- Cryo-installation upgrade needed (as documented in FP7 proposal Dec 2007)
- 2 CERN staff + 1 FSU in charge of SC test infrastructure and LHC exploitation !
- Number of prototypes
- LHC, SOLEIL experience showed approx 2.5 vertical measurements per validated cavity !
- Pre-series
- Big number for main series