

# CLIC MODULE INTEGRATION ISSUES



Alexandre.Samochkine @ cern.ch

# CLIC SYSTEMS



RF

MAGNET

INSTRUMENTATION

COORDINATE

SUPPORTING

ALIGNMENT AND  
STABILIZATION

BEAM FEEDBACK

VACUUM

COOLING

ASSEMBLY, TRANSPORT,  
INSTALLATION



Alexandre.Samochkine @ cern.ch

# CLIC MODULE



Module design is based on two-beam acceleration idea, where the RF power is generated by a high current e-beam (DB) running parallel to the MB. This drive beam is decelerated in special power extraction structures (PETS) and the generated RF power is transferred to the main beam (AS).


**Each system must be compatible with others, which makes both, the design and integration complex & challenging.**

**Baseline and alternative solution/s are being studied for each component of the technical system.**

**Many issues appear often during integration**


## THE MAIN TASKS OF INTEGRATION:

- overall layout,
- space reservation,
- number of components and their exact position and dimension
- system integration; interfaces between components, interference of components
- layout of special regions (i.e. DB turn-around loops)




## COLLABORATORS:

CEA/Saclay  
CIEMAT  
Dubna/JINR  
UH/VTT  
LAPP  
NTUA  
Pakistan, NCP  
PSI  
UPPSALA  
University of Manchester  
...




Alexandre.Samochkine @ cern.ch


# MODULE TYPES




Standard Module  
8374 per Linac



Module Type 3  
477 per Linac




Module Type 2  
634 per Linac



Module Type 4  
731 per Linac

## CLIC Module Type1 154 per Linac


**2 configurations under study**



**Tank Version**

**Sealed Version**

**current baseline**




AS: based on CLIC "G" disk damped (sealed version) (250 mm including 20 mm for interconnection)

+ special modules (damping region, modules with instrumentation and/or vacuum equipment)

DB (100 A)  
4 PETS, 2 Quads with BPM  
Each PETS feeds 2 AS


MB (1 A)  
8 acc. structures  
Main beam filling factor:  
91%






Alexandre.Samochkine @ cern.ch

# CLIC MODULES T0, T1 & T4




Standard Module

Module Type 4




Module Type 1






Alexandre.Samochkine @ cern.ch

# CLIC MODULE TYPE 1






Alexandre.Samochkine @ cern.ch



# RF SYSTEM



Alexandre.Samochkine @ cern.ch



# AS INTEGRATION




The design of the AS is driven by extreme performance requirements. The shape accuracy is relatively high (0.005 mm).

Several features of different systems, such as vacuum, cooling, WFM have to be incorporated into design. The damping waveguide loads are in between of them.

Two AS forming one Super-Structure  
( $\varnothing$  140 mm,  $L=2*230+20=480$  mm)




Detailed design under way




Alexandre.Samochkine @ cern.ch

# AS INTEGRATION




Super-AS with internal cooling

- COMPLEXITY**
- Brazed disks with "compact" coupler
  - Micro-precision assembly
  - Cooling circuits (400 W per AS)
  - Wakefield monitor (1 WFM per AS)
  - Vacuum system (10-8 mbar)
  - Interconnection to MB Q (stabilization!)
  - Structure support (alignment)
  - Output WG with RF components (e.g. loads)
  - RF distribution (CMRS w/CMF)




Super-AS with external cooling



Many systems to be integrated around the "Super-AS"







Alexandre.Samochkine @ cern.ch

# PETS INTEGRATION




## OLD

PETS octant (single bar)




Assembled in mini-tank





Equipped with couplers

Joined with AS via waveguides & choke mode flange






The octants assembly, mini-tank, on-off mechanism, vacuum system, cooling circuits, interconnection & supports are the subjects for integration

### ON-OFF MECHANISM



Welding






Alexandre.Samochkine @ cern.ch

# PETS INTEGRATION




## NEW


- Structure (8 octants) with "compact" couplers
- Mini-tank for structure
- On-off mechanism (  $t_{\text{off}} \rightarrow 20 \text{ ms}$  )
- Cooling circuits (size for 0.5% beam loss, couplers water-cooled, bars cooled by conduction)
- RF distribution to AS
- Vacuum system
- Interconnection to BPM
- Mini-tank support (fiducialisation)



Octants assembly



MINI-TANK




ACTUATOR

REFLECTOR

COOLING CIRCUITS

PETS "ON-OFF" mechanism combined with compact coupler

COMPACT COUPLER








Alexandre.Samochkine @ cern.ch

# RF SPLITTER WITH CMF





PETS (A) and AS (B) are connected via waveguides and RF splitter with choke mode flanges (CMF). CMF allows the power transmission without electrical contact between waveguides. This device should be flexible in order to permit independent alignment of two waveguides.



RF Design of CMRS  
(I. Syrathev & A. Cappelletti)

Requirements:  
WG interconnections between  
PETS and AS via CMF:


- X - shift:  $\pm 0.25$  mm
- Y - shift:  $\pm 0.5$  mm
- Z - shift:  $\pm 0.5$  mm
- Twist:  $< 5^\circ$



Hi Alexandre,  
it works even better  
than the one I sent  
you (input reflection  
is -54dB instead of -  
50dB).

Best regards,  
Alessandro.

RF splitter with Choke Mode Flanges





Alexandre.Samochkine @ cern.ch

# RF NETWORK DESIGN



Waveguide length optimization is based on losses, phase advance and RF to beam timing considerations.



A	B	C	D	E	F	G
1	WAVEGUIDE					
2	a	2.29E-02	m			
3	c	2.998E+08	m/s	Speed of Light		
4	f	1.1994E+10	Hz	CLIC frequency		
5	$\lambda_0$	2.50E-02	m	CLIC wavelength (c/f)		
6	$\lambda_{cutoff}$	0.04572	m	= 2 x a		
7						
8	WAVELENGTH					
9	$\lambda_{wg}$	2.985110E-02	m	$\lambda_{wg} = \frac{c}{f} \times \frac{1}{\sqrt{1 - (\frac{c}{2a \cdot f})^2}}$		
10						
11	GROUP VELOCITY					
12	vg	2.51E+08	m/s	$vg = c \times \sqrt{1 - (\frac{c}{2a \cdot f})^2}$		
13	vg/c	8.37328E-01				
14						
15						
16						
17	WAVEGUIDE LENGTH					
18	Las	0.25	m	AS Length		
19	Las x vg/c	2.09E-01	m			
20	Delay	8.339E-01	ns	$\frac{L_{as}}{c} \times 10^9$		
21	L2 - L1 = Las x vg/c	2.09E-01	m	= n x $\lambda_{wg}$		
22	n	7.0125E+00				
23	n real	7.0000E+00				
24	L2 - L1 corr	2.089577E-01	m		208.957	mm
25	ERROR	-1.490973E-03	ns			

442.541 1st waveguide length					
L11 =	442.541	1	PETS 1	wg1	
L21 =	651.498	2		wg2	
L12 =	592.512	1	PETS 2	wg3	
L22 =	801.469	2		wg4	
L13 =	442.541	1	PETS 3	wg5	
L23 =	651.498	2		wg6	
L14 =	592.512	1	PETS 4	wg7	
L24 =	801.469	2		wg8	




The breakdown detectors must be integrated



Alexandre.Samochkine @ cern.ch



# INSTRUMENTATION




# BEAM POSITION & WAKE FIELD MONITORS



Alexandre.Samochkine @ cern.ch

## WFM



Limited space for BPM integration:  
 60-100 mm, 1 BPM per Quad,  
 1 WFM per AS (RMS position error 5  $\mu\text{m}$ )  
**Qty:** DB:  $\sim 47000$ ; MB:  $\sim 151000$  units

## MB BPM


Choke BPM: RF design made,  
 mechanical design to be done  
 (possible collaboration with RHUL)  
 FNAL Low-Q cavity BPM: wakefield  
 calculation must be done very soon

## DB BPM



Design will start in 2010  
 (collaboration with SLAC)

**WFM:** Mechanical design under way  
 (collaboration with CEA-Saclay).  
 AS with WFM  $\rightarrow$  in 2010

## BPM




50x100 mm space on the side  
 along the module has been  
 reserved for the electronics  
 placement.



Detailed design is needed

Q-BPM interconnection must be studied





Alexandre.Samochkine @ cern.ch

# INSTRUMENTATION INVENTORY



## EDMS № 1009474

22-Jul-2009 AS, CG, GR, HMD, IS, KA, LS EDMS № 1009474

### Summary on CLIC Module (Type 1) instrumentation cables.

System	Number of signals	Qty of cables per module	Signal frequency	Frequency of read-out
<a href="#">Beam Instrumentation</a>	25	6		
<a href="#">RF components</a>	6	6		
<a href="#">Cooling</a>	72	2		
<a href="#">Alignment</a>	47	21		
<a href="#">Stabilization</a>	20	30		
<a href="#">Vacuum</a>	20	2		
<b>Sum</b>	<b>190</b>	<b>?</b>		


[BACK TO CONTENTS](#)



The signal and read-out frequencies still must be clarified and collected to the document.




Alexandre.Samochkine @ cern.ch



# MAGNET SYSTEM





Alexandre.Samochkine @ cern.ch


# QUADRUPOLES



**MB:** The magnets are needed in four different magnetic lengths (350, 850, 1350 & 1850mm).  
Baseline: the beam pipe is attached to the magnet. The beam pipe centre needs to be aligned to the magnetic centre of the quad with an accuracy better than 30  $\mu\text{m}$ . Transverse tolerance for pre-align. 17  $\mu\text{m}$  at 1s,  
Stabilization: 1nm >1Hz in vertical & 5nm >1Hz in horizontal direction at 1s.



**DB:** The active length specified is 150 mm. The total number of quads required for both linacs is  $\sim 42000$ . In current module design the DB Quad vertical size drives the beam height.

**DB**



**Drive Beam Quadrupole**  
Nominal Gradient: 67 T/m  
Magnet bore:  $\varnothing 23\text{mm}$

**MB**




**Main Beam Quadrupole**  
Nominal Gradient: 200 T/m  
Magnet bore  $\varnothing$ : 10 mm




Final 3D models for magnets needed  
→ to be compatible with space allocation






Alexandre.Samochkine @ cern.ch

# MODULE OVERALL DIMENSIONS



**Nov-2008**



**Oct-2009**


WIDTH: **1160 vs 1525**  
 BEAM HEIGHT: **620 vs 730**

Direct influence on alignment,  
 stability, transport and installation






Alexandre.Samochkine @ cern.ch



# SUPPORTING SYSTEM




Alexandre.Samochkine @ cern.ch

# SUPPORTING SYSTEM



**BASELINE:**

- MB girders are not of the same length
- MB Q support interrupts the MB girder
- MB Q beam pipe and AS are connected by bellows






Alexandre.Samochkine @ cern.ch


# SUPPORTING SYSTEM



Current baseline is to support the AS and PETS with V-support connected to the SiC girder with rectangular cross-section.




AS support



PETS support

Different shape configurations of the girders are considered. The girder material properties must provide a compromise between damping and stiffness (under investigation in a contact with several companies).

Supports must be compatible with thermal loads. The structures must stay within longitudinal and transversal tolerances under variable beam-loading conditions.




Alexandre.Samochkine @ cern.ch

# SUPPORTING SYSTEM



**Requirement:**  
possibility to align  
MB & DB separately


Under design,  
will be  
finalized with  
precision  
assembly  
study of AS




Space is reserved for MB Quad support (including alignment/stabilization/support) and alignment system



Alexandre.Samochkine @ cern.ch



# VACUUM SYSTEM




Alexandre.Samochkine @ cern.ch

# VACUUM LAYOUT



Consideration on the quantity and overall dimensions of devices needed for creation and maintaining vacuum for the experiment is shown schematically.

## BASELINE: $10^{-8}$ mbar




Sectoring valves must be integrated

LEGEND	OBJECT	QUANTITY	SIZE (mm)	WEIGHT
Q	Quadrupole			
Mobile TM Station	Mobile Turbo Molecular Station	3-6 stations/sector, 40 in total	500x500x900	
S P	Sublimation Pump	4/module [MB-2, DB-2]		
I P	Ion Pump	3/module [MB-1, DB-1 or 2*]	152x310x240	20 kg
⌵	Manual Valve	3/module [MB-1, DB-1 or 2*]		

\* - depends on Quad Vacuum Chamber cross section






Alexandre.Samochkine @ cern.ch

# VACUUM




Vacuum system is under optimization




$$S=0,47 \text{ m}^2$$

Rough calculation of AS surface for pumping is done.

The more precise (with the loads surface) must be finished as soon as the AS design done.



The Quad vacuum chamber must be integrated.  
Vacuum components supporting, decoupling from AS & PETS  
are our current challenging tasks.




# VACUUM INTERCONNECTIONS



Alexandre.Samochkine @ cern.ch

Drive beam – QUAD/PETS intermodule interconnections




The MB and DB vacuum coupled via the common manifold and WG

The vacuum interconnections (intra-/inter-module):


**MB:** non-contacting interconnects acceptable. Short range wake-fields essentially equal to an iris. Long range wake-fields need damping. (under optimization)

**DB:** good contact is necessary due to high current.


Interconnections - Drive beam




Drive beam – QUAD/PETS intramodule interconnections



Drive beam – PETS/BPM intramodule interconnections



Drive beam – QUAD/PETS intramodule interconnections




Concepts by C. Garion ready for detailed mechanical design study and implementation in the modules.




To be integrated ASAP



Alexandre.Samochkine @ cern.ch



# ALIGNMENT & STABILIZATION SYSTEM



Alexandre.Samochkine @ cern.ch

# ALIGNMENT




Mechanical pre-alignment within  $\pm 0.1$  mm (1s)  $\rightarrow$  Active pre-alignment: within  $\pm 10$   $\mu$ m (3s)

Concept: straight alignment reference over 20 km based on overlapping references


- AS and PETS pre-aligned on independent girders (mono-girder alternative is also considered)
- «Snake system», validated in CTF2. (Scaling needed due to higher load)
- MB Quad pre-aligned independently.

## To be considered in integration:

- Integration of the pre-alignment system/s in the modules,  $\Rightarrow$  transport and installation
- Fiducialisation (design and tests)



Space reservation for the alignment equipment



Alexandre.Samochkine @ cern.ch

# STABILIZATION






Stabilization requirement for the MB Quad (vertical tolerance:  $1 \text{ nm} > 1 \text{ Hz}$ )  
Compatibility of stabilization and pre-alignment systems to be considered

### TWO OPTIONS:

CERN: rigid (active stabilization + fast nano-positioning)

LAVISTA: soft support




A proposal for the MB Quad fine alignment and stabilization has been suggested previously. Space is reserved accordingly. The problem is under study.



The detailed study of vibration from different kind of sources as well as the components modal behaviour must be accomplished before integration of the MB Quad stabilisation system in the module .




Alexandre.Samochkine @ cern.ch



# COOLING SYSTEM




# MODULE COOLING LAYOUT




- **MB** - AS in series, loads in series, Quad - in parallel
- **DB** - PETS in series, Quads in series

The water circuits have a common inlet and outlet. Loads dimensions are adapted to the current module configuration and do not exceed 300mm in length and  $\varnothing$  50mm.



Valves still have to be integrated



An example of cooling circuits routing

Due to high power dissipation:  
RF structures and magnets are water cooled.  
RF network must maintain its correct electrical length.



(RF network cooling to be confirmed)



# PETS COOLING


Baseline:

- cooling circuits external to PETS
- cooling of PETS in series




**OLD**

Forced convection cooling – circuits inside the vacuum tank, outside the octants



**NEW**




New cooling configuration


Cooling channel and tubes integrated into compact coupler.



Alexandre.Samochkine @ cern.ch



# ASSEMBLY, TRANSPORT, INSTALLATION



Alexandre.Samochkine @ cern.ch

# MODULE TRANSPORT & INSTALLATION



The module assembly will be done on the surface. Each module has the cradles only on one end => the temporary support is needed. Strategy for Q modules to be agreed with SWG.

An agreed strategy (with CES WG) is based on overhead lifting with spread beam. The two beams must be rigidly bound in order to maintain the alignment during transport (our concern – dedicated test in girder mock-up). The aim is to transport already interconnected modules.

The vertical interconnection plane between adjacent modules is included in integration requirements. (inter-girder connection: 30 mm)

The required space has been reserved for the alignment system. And we have to cross these zones during installation.

The lifting points still must be defined.

- The transport solution needs to be in compliance with systems' components.
- The test area must be compatible with transport and installation tests requirements.
- The transport and installation issues must be studied at the current design phase.



Alexandre.Samochkine @ cern.ch

# CONCLUSIONS



- Integration of different systems in terms of space reservation has been finished.
- Detailed design started for the main systems.
- PETS concept is well advanced including the On-Off mechanism.
- AS layout is under way. Integration conditions are specified. The system is very complex for design and integration. This is due to necessity to have many systems attached to AS.
- Magnets dimensions should be confirmed soon.
- RF network is well advanced.
- PETS concept is well advanced including the On-Off mechanism.
- The detailed design for supporting system is needed for better understanding of integration issues.
- This is valid for the alignment and stabilization systems' components as well.
- The vacuum parts are defined, but the neighboring components give some restrictions. The optimization will be continued.
- The instrumentation components design would require more attention.
- Transport features to be studied and implemented.

**Overview of the module systems now. Review in the nearest future (by Dec-2009).**

**Module baseline design definition by the end of Mar-2010.**

**CLIC modules in the lab from 2010**

**Test modules in CLEX from 2011**




Alexandre.Samochkine @ cern.ch

# GRATITUDE



I am very much obliged  
to each system responsible  
and all collaborators  
for their contribution & cooperation !





**THANK  
YOU !**


**THE END**




Alexandre.Samochkine @ cern.ch

# EXTRA SLIDES








VAC.  
RESERVOIR



Depending on manufacturing strategy the AS could be produced of four quadrants, later assembled together.





Alexandre.Samochkine @ cern.ch

# TEST MODULES INTEGRATION STUDY

