

**ESS**  
**BITBAO**

## **News from ESS**

**Cristina Oyón, Mats Lindroos, Steve Peggs**

**November 2009**



## ESS OVERVIEW

- *ESS-S and ESS-B have become **ESS** which now has **13 future member states***
  - ***Main site for facility in Lund in Sweden***
  - ***Complementary R&D and user centre in Bilbao in Spain***
- ***First neutrons for 2018 with full design specifications in 2023***
  - *Ambitious goals requires ambitious planning*
- ***Build on latest SC RF R&D***
  - *Requires high reliability and low losses*
- ***Maximize synergies with other similar projects***
  - *Cost and time gains*
  - *Trained people are in short supply*
- ***Very challenging task...***
  - *That is our job...*
  - *...and that is why we are here!*



# FACILITY TECHNICAL OBJECTIVES

*5 MW*

*Long pulse source*


*$\leq 2$  ms pulses*

*$\leq 20$  Hz*

*Protons ( $H^+$ )*

*Low losses*


*High reliability  $>95\%$*



**ESS**  
bilbao



# BUDGET



**Facility investment: 1.377 M€<sub>2008</sub> with 22 instruments  
+ 101 M€<sub>2008</sub> site specific cost**

**Operational cost: 89 M€<sub>2008</sub> per year**

**Decommissioning cost: 344 M€<sub>2008</sub>**




# 1st STEERING COMMITTEE


- *Held in Copenhagen 22-23 October 2009*
- *Delegates from 13 countries: **Denmark, Estonia, France, Germany, Iceland, Italy, Latvia, Lithuania, Norway, Poland, Spain, Sweden, Switzerland***
- *Agenda:*
  - *governance of ESS*
  - *organisation of ESS*
  - *TAC & SAC*
  - ***ESS Design Update***
  - *administrative issues*



# DESIGN UPDATE




# DESIGN UPDATE




# LINAC DESIGN UPDATE

**Objective:** To present a **Conceptual Design Report** with full cost (to completion) for the linac by the end of 2012

- Collaborations between institutes and universities in the ESS countries
- Agreement of main linac parameters with target and instrument teams







*In comparison to the originally proposed design (5 MW, 1 GeV, 150 mA, 16.7 Hz) the parameters have been modified in order to **simplify the linac design** and to **increase reliability**. In essence the current has been decreased and the final energy has been increased, keeping the footprint of the accelerator the same.*

- ✓ **Increase in energy** – With increased energy the average pulse current can be reduced by the same factor.
- ✓ **Increase of the cavity gradient** – By decreasing the current to 75 mA, the gradient can be raised to 15 MV/m, keeping the coupler power constant at 1.2 MW.
- ✓ **Increase of beam energy** - the final energy was increased from 1 to 2.2 GeV.
- ✓ **Repetition rate** - The originally proposed repetition rate of 16.67 Hz has been increased to 20 Hz.
- ✓ **Pulse length** - The originally proposed pulse length of 2 ms has been reduced to 1.5 ms

# ESSS PREPARATORY WORK

*Work with expert group (the ESSS linac reference group)*




Table 1: Primary ESSS performance parameters in the long pulse conceptual design. There is no accumulator ring.

INPUT		Nominal	Upgrade
Average beam power	[MW]	5.0	7.5
Macro-pulse length	[ms]	2.0	2.0
Pulse repetition rate	[Hz]	20	20
Proton kinetic energy	[GeV]	2.5	2.5
Peak coupler power	[MW]	1.0	1.0
Beam loss rate	[W/m]	< 1.0	< 1.0
OUTPUT			
Duty factor		0.04	0.04
Ave. pulse current	[mA]	50	75
Ion source current	[mA]	60	90
Total linac length	[m]	418	418

## DESIGN UPDATE: SOME ISSUES

### *Question for future users and ESS technical teams:*

- *Using the best SCRF technology, what is the **optimum design** of the linac with given objectives?*
- *How long is the **ideal “long pulse”** and what is the **ideal repetition rate**?*
- *Can we confirm that the number of **neutron at the instruments** is proportional to the proton-Joules delivered at target for **energies up to 3 GeV** or more?*
- *What flexibility can be left in the design for **future upgrades** without compromising construction time, schedule and budget?*




**ESS**  
bilbao




# COLLABORATION MODEL FOR LINAC DESIGN


- *A strong **coordination team** in Lund – responsible for project integration*
- *A **collaboration board** – to assure good coordination*
- *Adoption of **common standards***
- *Regular **reviews***
- *Basis for **collaboration during construction phase***
- *Share of technical resources with **XFEL, SPL, Project X, eRHIC....***



# CORE TECHNOLOGY REVIEW



# R&D FOR DESIGN PHASE



# WORK PACKAGES


- 1. Management Coordination***
- 2. Beam Physics***
- 3. Infrastructure Services***
- 4. SCRF Spoke cavities***
- 5. SCRF Elliptical cavities***
- 6. Front End and NC linac***
- 7. Beam transport, NC magnets and Power Supplies***
- 8. RF Systems***



**ESS**  
bilbao



## 4TH LINAC REFERENCE GROUP MEETING



- Held in **Aarhus, Denmark** the **9th October**
- Focus on the low energy part of the linac, in particular the **low beta SC part**
- ~30 experts attended from: **FNAL, INFN, TSL, CERN, MSL, JLAB, SNS, SOLTAN, ANL, BNL, AU, CEA, UU, ESS**
- **Talks:**
  - low beta structures – Duperrier (CEA/IRFU)
  - low beta NC linac design philosophy – Stovall
  - SPES pulsed linac – Pisent (INFN)
  - JLAB experience on SC low beta structures – Delayen (JLAB)
  - The all SC linac, ANL view – Ostroumov (ANL)
  - EURISOL spoke cavity development – Bousson (CEA)
  - An optimised spoke option for ESS in 50-160 MeV range – Eshraqi (ESS)




**ESS**  
bilbao





# 5TH LINAC REFERENCE GROUP MEETING

- To be held in **Bilbao** on the **23rd November**
- Focus on **beam losses & operational simulations**
- Goal: to identify key operational scenarios and beam dynamic issues that permit **low beam losses, rapid commissioning and high reliability**
- Outcome expected: **connections** between these 3 issues outlined in **work programmes** for ESS design update



**ESS**  
bilbao