

# XFEL: cryomodule assembly at CEA/Saclay

- *XFEL facility & Superconducting linac*
- *Main assembly steps*
- *Industrial operation at Saclay*
- *Preparation of the infrastructure*
- *Plans and Schedule*


# European-XFEL

The European XFEL is a new research facility currently under construction in the Hamburg area in Germany. From 2014 on, it will generate extremely intense and ultra short X-ray flashes.

European  
XFEL




**Web link: <http://www.xfel.eu/>**





Frequency of flashes	30 000 per second
Wavelength	0.1 to 6 nm
Flash duration	< 100 fs
Brilliance (peak value)	$5 \cdot 10^{33}$ (photons / s / mm <sup>2</sup> / mrad <sup>2</sup> / 0,1% bandwidth)
Brilliance (aver. value)	$1.6 \cdot 10^{25}$ (photons / s / mm <sup>2</sup> / mrad <sup>2</sup> / 0,1% bandwidth)

- On 8 January 2009, civil engineering work (tunnels, shafts, halls) has been started at all three construction sites
- International state convention for the foundation of the European XFEL GmbH on 23 September 2009 in Berlin initiated by the representatives from the currently 13 partner states
- Official registration of the 'European X-Ray Free-Electron Laser Facility GmbH', into the Commercial Register of the Hamburg District Court on 08 October 2009

# XFEL: the Superconducting linac




Linac and cavity parameters	
Energy	17.5 GeV
$I_{\text{beam}}$	5 mA
$f_{\text{RF}}$	1300 MHz
$f_{\text{rep}}$	10 Hz
$t_{\text{RF}}$	1.4 ms
$t_{\text{beam}}$	0.650 ms
Total length	2.1 km
Acceleration length	1.7 km
Cavity gradient	23.6 MV/m
$P_{\text{RF}}$ / coupler (pk, av.)	120 kW, 1.7 kW



**Superconducting linac**  
**= 101 cryomodules**  
**= 808 9-cells cavities +**  
**808 couplers & tuners & ...**

# XFEL: Cryomodule Assembly



- Sequences of cryomodule assembly were optimised at DESY and took benefit from assembly of several TTF and FLASH cryomodules.
- Assembly sequences qualified by:
  - Results of RF tests performed at DESY
  - Operational performance on FLASH
- These main sequences are kept unchanged for the assembly of XFEL cryomodules at Saclay



# Cryomodule Assembly: main sequences (1)

In clean room class 10 (ISO4):


Assembly of the components sealing the cavity vacuum:

Cavities, bellows, cold part of the couplers, end-group, valves

l r f u  
cea  
saclay



*From assembly of Module 8 at DESY (April 2009)*





# Cryomodule Assembly: main sequences (1bis)

- Cavity string =
- vacuum valve
  - 8 cavities (in their LHe tank) with bellows
  - end group = Qpole + BPM
  - HOM tube
  - vacuum valve



*End of cavity string assembly in DESY clean room*



# Cryomodule Assembly: main sequences (2)

Outside the clean room (on the same rail):  
Assembly of components fixed to the cavity (Helium tube, magnetic shielding, SI, tuners, ...)

l r f u

cead

saclay





*From assembly of PXFEL1 at DESY (May 2009)*



# Cryomodule Assembly: main sequences (2bis)

Outside the clean room (on the same rail):  
Connection to cold mass


l r f u  
ceea  
saclay



*From assembly of PXFEL1 at DESY (May 2009)*



# Cryomodule Assembly: main sequences (2ter)




- Assembly of the cold part (cavity string + cold mass) of the cryomodule almost completed at this stage.
- Cavity string disconnected from the support posts



*From assembly of PXFEL1 at DESY (May 2009)*

# Cryomodule Assembly: main sequences (3)



- The whole part can be moved with a crane to an **area equipped for alignment** of the cavities + end-group (tol. <math>< 500 \mu\text{m}</math>)
- Further assembly (thermal shields and braids, cabling, welding, SI,...)
- Assembly of the cold part is now completed and ready to be moved into the vacuum vessel with the **cantilever**





# Cryomodule Assembly: final sequences




After assembly of the warm part of the couplers & the last connections, the cryomodule is ready for shipment



*Cryomodule 8 with caps and frame at Saclay before transport to DESY*



# Assembly: Industrial operation at Saclay



CEA committed to supervise  
the assembly of 3 pre-series and 100 series XFEL cryomodules  
at Saclay

Cost book 2005	WP3a Cold Mass Fabrication		WP3b Module Assembly & Installation		WP5 Coupleurs RF		WP9 Assemblage Trains de Cavités	
	M&S	FTE	M&S	FTE	M&S	FTE	M&S	FTE
<b>DESY</b>	25%	51%	4%	61%	20%	20%	3%	44%
<b>INFN</b>	25%	16%	-	-	-	-	-	-
<b>CEA</b>	50%	33%	96%	39%	-	-	97%	56%
<b>IN2P3</b>	-	-	-	-	80%	80%	-	-

## The main requirements:

- Assembly of cavity string in clean room ISO 4
- Production throughput of 1 CryoModule / week

## Preparation of the industrial operation at Saclay:

- Industrial pre-study (2008)
- Study and order of the 'big' tools (2009-2010)
- Complementary industrial study "EPPS" (starts in January 2010)

# Assembly: Industrial Operation at Saclay

Industrial pre-study in 2008 (Thalès): defining the infrastructure and establishing the fabrication folder

- identification of the Work Stations
- definition of equipments and tools
- storage of big CryoMod parts and warehouse
- composition of the working teams
- preliminary schedule over one week
- preliminary risk analysis (back up WS, redundancy)

**Main outcome: the drawings of the clean room were modified in order to meet the requirements of the Op.**


- a second rail be implemented in CR
- a dedicated area for assembly of coupler with cavity is created
- components are introduced into CR through a cavity washer (ISO4)



# Clean room: work flow


## Inventory of pieces entering or exiting the CR each week:

- A- Cavity x 8 ; Coupler cold part x 8 ; End-group
- B- 200 tools (valves, posts, fixtures, ...) ; 1200 pieces (bolts, nuts, gaskets, ...) ; consumables (gloves, wipes, ...)
- C- Cavity string with posts ; broken pieces ; waste




# Clean room: coupler work station

As a consequence of the production throughput, a dedicated work station is added for assembly of couplers with cavities




# Clean room: how many work-stations in the CR ?



As a consequence of the production throughput, cavities for 4 successive strings are in the CR



# Infrastructure: clean room (as built)



# Assembly: Industrial Operation at Saclay

Industrial pre-study in 2008 (Thalès): defining the infrastructure and establishing the fabrication folder

- identification of the Work Stations
- definition of equipments and tools
- storage of big CryoMod parts and warehouse
- composition of the working teams
- preliminary schedule over one week
- preliminary risk analysis (back up WS, redundancy)


## **Other main outcome: selection of one configurations of work stations amongst several**

- easy access to each of the workstation from the central court
- the moving of all parts from their actual WS to the next is possible within one day (working hours)
- the whole area can be delimited (XFEL Village)




# Final configuration of Work Stations

l r f u  
cea  
saclay




# Definition of the other Work Stations



# Optimisation of long parts flow

CEA



1 day (7:00 to 16:00) a week is dedicated to moving successively all parts from their actual WS to the next



## **Preparation of the infrastructure:**

- Clean room available very soon (Nov. 09)
- Completion of renewing of assembly halls expected in 2 months
- Delivery of the big tools in March 2010

## **Preparation of the industrial Op. :**

Complementary industrial study “EPPS” should start in Jan. 2010.

Industrial operation at Saclay:

- Assembly of the 3 pre-series cryomodules in 2011 (2<sup>nd</sup> sem.)
- Assembly of 100 cryomodules (ramp-up and production) from 2012 to 2014.

# Concluding remarks

**All the procedures and sequences of assembly were intensively optimized at DESY this last decade**

**Definition of Saclay Infrastructure was strongly impacted by the production throughput of 1 cryomodule / week**

**Reference procedures will benefit on other projects:**

- **assembly of long cryomodules  
(e.g. 15 m long SPL cryomod.)**
- **clean room assembly**
- **cavity preparation**

**Many thanks to all the colleagues from Saclay and DESY who have compiled all the documents (and much more ...) presented in this talk**

**Special thanks to: S. Berry, C. Madec and O. Napoly**

**and thank you for your attention**