



# SPL cavity design by IPN Orsay

Guillaume OLRÉY

# Outline

---

Introduction

RF design

Planning

# Commitment within



## **WPI I: SRF: SC RF technology for higher intensity proton accelerators & higher energy electron linacs**



### **Task 4: SC Cavities for proton linacs**

- Design, fabrication and tests of  $\beta=0.65$  and  $\beta=1.0$  cavities with the goal to reach announced performances.
- [...]




**Sub-task I:** Design and fabrication of  $\beta=0.65$  704 MHz elliptical cavity equipped with a Titanium helium reservoir. Preparation (BCP, HPR) and assembly in clean room.  
[...] Test of the cavity in vertical cryostat [...].


# RF parameters

**Table 4.11:** SPL superconducting linac design parameters

Maximum peak surface electric field	50 MV/m
Maximum peak surface magnetic field	100 mT
Cavity quality factor at 2 K	$\geq 10^{10}$
Accelerating gradient ( $\beta = 0.65$ )	19 MV/m
Accelerating gradient ( $\beta = 1.0$ )	25 MV/m
$R/Q$ ( $\beta = 0.65$ )	290 $\Omega$
$R/Q$ ( $\beta = 1.0$ )	570 $\Omega$
Frequency	704.4 MHz
Number of cells	5



**Test results of 704 MHz, 5-cell, beta 0.65**




“Performance Improvement of the Multicell Cavity Prototype for Proton LINAC Projects”, B. Visentin et al., LINAC 2004

Conceptual design of the SPL II, CERN-2006-006

**Table 4.9:** Medium- $\beta$  multi-cell cavity parameters (bulk-niobium structures only)

Project	$f$ [MHz]	$\beta$	$E_{peak}/E_{acc}$	$H_{peak}/E_{acc}$ [mT/(MV/m)]	$N_{cell}$	$(R/Q)/N_{cell}$ [ $\Omega$ ]
RIA	805	0.47	3.34	5.94	6	26.67
TRASCO	704	0.47	3.57	5.88	5	31.60
SNS medium- $\beta$	805	0.61	2.71	5.72	6	46.50
CEA/CNRS	704	0.65	2.60	4.88	5	63.00
SNS high- $\beta$	805	0.81	2.19	4.72	6	80.50
TTF	1300	1.00	2.00	4.16	9	115.11


( $R/Q$ ) uses the ‘linac’ definition.




$E_{pk}/E_a < 2.63$   
 $B_{pk}/E_a < 5.26 \text{ mT/MV/m}$

# Starting from 2D to 3D


- 1999: Cavity design with SUPERFISH with no RF coupler and HOM ports





- 2009: New 3D model with Microwave Studio




# EM fields – fundamental mode




Electric field



Magnetic field




# RF parameters





- Field flatness < 5%
- Cell-to-cell coupling=0.74%

- Half-cell close to RF coupler adjusted for field flatness  
 $\Rightarrow 0.2 \text{ mm} \rightarrow +28\%$




# RF parameters (con't)



f (MHz)	703.5	too be matched
$E_p/E_{acc}$	3.11	too high
$B_{pk}/E_{acc}$ (mT/MV/m)	4.95	Ok
r/Q (Ohm)	352	Ok
G (Ohm)	200	Ok
Vacc @ $\beta_{opt}$ & 1 Joule (MV)	1.26	Ok
$Q_o$ (@2K, $R_{res}=2n\Omega$ )	$4 \cdot 10^{10}$	Ok



# External coupling $Q_{ext}$




- Goal:  $Q_{ext}=9.7 \cdot 10^5$  with  $\varnothing_{ant}=43.5$  mm and  $\varnothing_{port}=100$  mm

Parameters:

- $\varnothing_{beam\ tube}=120$  mm
- $L_{ant}=151$  mm (1 mm of penetration inside beam tube)
- $D_p=72$  mm

# Preliminary drawings

- No flanges, no Helium reservoir



# Planning

---

2009

*End of November:* finish RF design, check HOM's

*Mid-November to end of December:* mechanical calculations, design of the Helium tank, check the interfaces with the cryomodule (integration of the CEA-type tuning system, and RF coupler)

2010

*End of January:* technical drawings ready for production, technical specifications for fabrication, Niobium order (3/4 months, ~40 k€)

*February to mid-March:* cavity call for tender

*End of March:* choice of the manufacturer

*Mid-April:* kick-off meeting, beginning of the fabrication (~8 months).



# Thank you for your attention

---

IPN Orsay team

RF: D. Longuevergne (PhD), F. Bouly (PhD)

Mechanics: H-M. Gassot

CAD: S. Rousselot