



AD Outlook for 2010




Key dates for 2010 run:

- 22/3 start of HW-tests
- 12/4 start s-u with beam
- 10/5 Start of physics

⇒

- 28 weeks of physics scheduled (4600 h)





- **Experimental requirements for 2010:**
- **ACE:**
 - 2-3 * 24h periods mid-June
 - 1 week 24h/24 in October
 - Single bunch ejection at 500 MeV/c (no e-cooling)
- **ALPHA, ATRAP: Single bunch ejection at 100 MeV/c**
- **ASACUSA: Single and 6:ple ejection at 100 MeV/c**
- **3*8 h shifts**
- **AEGIS: No beam required in 2010**



AEGIS (AD-6)

- Gravitational studies of Hbars produced in flight
 - Sharing of the DEM-zone with ACE (cell irradiation)
 - Fully approved in 2009
 - Installation and commissioning in 2010
 - First Pbar beams in 2011
- => one more user to share the available Pbars





AEGIS schedule

2009	2010	2011	2012	2013	2014	2015	2016	milestone
construction of the three magnets (5 T, 1T, 0.15 T)								commissioning of the magnets
purchase of the positron source and accumulator	commissioning		e+ studies	e+ studies	e+ studies	e+ studies	e+ studies	commissioning of the accumulator
construction and assembly of the traps and controls								
refurbishing of central detector, incl. positronium detection	commissioning							source and in-situ cosmics/pbar/e+ tests
	assembly and commissioning with e-, e+ and antiprotons							particle trapping and manipulations
		antiproton trapping						detector test with slow antiprotons
Positron excitation lasers: construction, commissioning and installation								laser wavelengths and power
		positronium production						Positronium and first Rydberg positronium*
construction of the dilution refrigerator	commissioning and optimization of the dilution refrigerator							refrigerator reaches 0.05 K*
		further lasers: installation & comm.						
			antihydrogen and beam					Antihydrogen temp.* & first Antihydrogen beam production*
construction and assembly Moiré deflectometer	tests and gravity measurement with Ar atoms and commissioning in situ							gravity measurement with Ar atoms
				(anti)hydrogen beam gravity measurement				first Antihydrogen gravity measurement*
	construction and assembly of decelerator & trap		tests of deceleration and magn. trapping					trapped Hydrogen
					tests of deceleration and magn. trapping			trapped Antihydrogen*
			construction and commissioning of pulsed Lyman- α laser (radial cooling of antihydrogen)			cooling of trapped Antihydrogen		cooling* and spectroscopy*
							improved gravity meas.	impr. cold Antihydrogen gravity measurement*
								* PhD thesis topics



AEGIS beamline in AD and DEM zones







• AEGIS beamline equipment:

• Extension of beamline in DEM-zone used by ACE

• Upgrade of MWPC:s in all ejection lines: GEM detectors + new electronics

Magnets						
<i>Element</i>	<i>Type</i>		<i>Bl [Tm]</i>	<i>I [A]</i>	<i>I_{max}</i>	
DEM.DHV32	PSB Type 1		0.0081/0.0079	+ -10	10	
DEM.BHZ35	MEA43		0.175	73	80	
DEM.DHV52	PSB Type 1		0.0081/0.0079	+ -10	10	
<i>Element</i>	<i>Type</i>		<i>K1 [m⁻²]</i>	<i>GL [T]</i>	<i>I[A]</i>	<i>I_{max}</i>
DEM.QN40	QTR		0.2548	0.091	8.9	50
DEM.QN50	QTR		0.5550	0.1981	19.4	50
Power converters						
<i>Element</i>	<i>Type</i>		<i>I nominal [A]</i>	<i>I_{max} [A]</i>		
DEM.DHZ32	LPSS 35V 24A		0	+ -24		
DEM.DVT32	LPSS 35V 24A		0	+ -24		
DEM.BHZ35	2*60V/100A		73	+ -100		
DEM.QN40	LPSS 18V 50A		8.9	+ -50		
DEM.QN50	LPSS 18V 50A		19.4	+ -50		
DEM.DHZ52	LPSS 35V 24A		0	+ -24		
DEM.DVT52	LPSS 35V 24A		0	+ -24		
MWPC/GEM detectors						
DEM.MWPC33						
DEM.MWPC37						
DEM.MWPC54						
Vacuum equipment						








Beamline schedule

- Final layout/optics 1 Sept 09
- Final mechanical design + drawings 1 Nov 09
- Vacuum chamber fabrication 1/11/2009 -1/3/2010
- Magnet refurbishing/tests =>1/3/2010
- Power converter refurbish/purchase 2009/2010
- MWPC/GEM tests =>1/11/2009
- Installation: shutdown 09/10
 - MWPC electronics (started Aug .09)
 - MWPC chambers
 - Vacuum chambers/equipment
 - Magnets
 - Power converters/cabling/controls+ during 2010 run



- Progress:
- Shutdown 2010, phase 1:
 - Finish all installation work inside AD ring enclosure before startup
- During 2010 run, phase 2:
 - Installation in DEM-zone (access ok)
 - Equipment tests



- Removal of 20T concrete pillar supporting ATRAP2 positron accumulator zone
- Replaced by metallic structure to make space for AEGIS equipment
- It went well.....





ELENA

- **SPSC request:**
- We have already identified 2 points which will require some attention, namely:
 - - a better quantification of the gains for the experiments, with some real practical examples for each of them ;
 - - the implications of an improved AD on the experimental area in order to be able to host more experiments.




ELENA location

- Building 193
- Building 181
- New building
- Conclusion



ELENA location 1: Initial place






ELENA location 1: Initial place

- + Short transfer lines
- + Few new magnets
- + Lowest cost
- + No AD ring modifications
- + No change for the present experimental zone (low and high energies possible)
- + New experimental zone at low energy obtained with some difficulty (transfer line + shielding under user barrack, access)
- o Modification of ASACUSA experimental zone
- - Tight space (no upgrade possible, difficulties for ELENA installation and access)
- - 4 kicker modules instead of 2 to move
- - Difficult to modify shielding
- - Perturbations to 4 users during installation



ELENA location 2: New place in Bldg193






ELENA location 2: New place in Bldg193

- + Plenty of space (future upgrade possible)
- + Easy access (no particular re-arrangement in AD hall needed)
- + No perturbation to existing ejection lines and shielding
- + New experimental zone at low energy possible
- + No change for the present experimental zone (low and high energies possible)
- + Simple transfer line to new zone

- - Move racks, new cabling – cost?
- - New low energy septum magnet (+kicker?)
- - Long 100keV transfer line (stability?)

ELENA location 3: Building 181






ELENA location 3: Building 181

- + Space for future upgrade and a new e+ source (1000m² or more, max. 2600m²)
- + Keep high energy experiments in Bldg 193 and low energy experiments in new location
- + No modifications in AD ring
- + Several new experimental zones at low energy possible
- + No perturbation to existing experiments during ELENA construction and commissioning
- - Very long 5MeV beam line, expensive
- - Civil engineering work (>100m long new tunnel, max. 10% slope) – expensive (cost of about 8-10 MCHF)
- - Long downtime for moving and restarting experiments (+6 months?)
- - Bldg 181 presently used for other activities (LHC magnet assembly press, workshops, clean room)

ELENA location 4: New Building





ELENA location 4: New Building

- + Plenty of space for future upgrade and for a new e+ source (better layout, 2200 m²)
- + Keep high energy experiments in Bldg 193 and low energy experiments in new location
- + Short new 5MeV extraction beam line
- + No modifications in AD ring
- + Several new experimental zones at low energy possible
- + No perturbation to existing experiments during ELENA construction and commissioning
- - New expensive building (cost of about 15-20 MCHF and delay of the project by about 1.5 years)
- - Long downtime for moving and restarting experiments (+6 months?)



Conclusion

- + Plenty of space (future upgrade possible)
- + New experimental zone at low energy possible with a very simple transfer line
- + Easy access (no particular re-arrangement in AD hall needed)
- + No perturbation to existing ejection lines and shielding
- + No change of the present experimental zone (low and high energies possible)

- Many advantages, small number of disadvantages show that location 2 is very attractive and very elegant place to put ELENA.



ELENA location 2: New place in Bldg193

