
High power RF tests places at CERN

O. Brunner, CERN

Scope of the presentation

- ❑ High power and SCRF activities @ CERN
- ❑ Existing infrastructures
- ❑ SPL cryomodule tests
- ❑ Conclusions

High power and SC RF activities (1)


- High power RF
 - LHC
 - 400MHz, 330kW CW, 16 power stations in LHC + 2 test stations
 - Linac4
 - 352MHz, 1.3/2.8 MW, 19 future power stations + 2 (3) test stations
 - CLIC&CTF3
 - 3GHz, 45 MW, 1.5GHz, 25 MW, 13 power stations + 1 place
 - 12GHz, 50MW, 1 test station
 - LEP RF equipment tests for external requests
 - 352MHz, almost finished
 - SPL test stand
 - 704 MHz, \approx 1MW, 50 Hz, 1 future test stand
 - Crab cavities
 - Under study..

High power and SC RF activities (2)


- SC cavities & Cryomodules
 - LHC
 - 4 cryomodules in LHC, 1 spare + 1 spare cavity (to be tested)
 - 3 spare cavities to be built & tested (2011-2012)
 - HIE Isolde
 - 32 cavities to be built & tested
 - 5 cryomodules to be assembled & tested
 - SPL
 - 4 cavities to be built & tested
 - 1 cryomodules to be assembled & tested
 - CLIC & CTF3 structures
 - RF structure assembly in clean rooms

Available infrastructure (1)

- Building A5:
 - LHC & Linac4 High Voltage
 - Klystron modulators, fast protection systems, klystron HV tanks
 - 100kV, 15mA power supply
- Building 112:
 - LHC & Linac4 High Power RF
 - Tests of klystrons, circulators, WG, HV equipment, controls
 - LHC power coupler tests
 - 100kV, 20A power supply, Linac 2Hz modulator (ready by the end of 2010)
- Building 152:
 - Linac4 3MeV test station
 - Tests of Linac4 3MeV section (in 2011) + some L4 RF structures (2010 ->?)
 - Complete Linac4 2Hz power station (modulator, klystron,..)
- Building 252:
 - SC cavities coating & clean rooms
 - LHC, HIE Isolde, SPL
 - Nb deposition system for HIE Isolde cavities (system for LHC cavities to be re-installed)
 - Low pressure ultra pure water rinsing (max 10 bars)
 - Two clean room (class 100, 10)
- Building 118 (vacuum group):
 - Chemical treatments
 - LHC, HIE Isolde, SPL + many other activities
 - EP station
 - High pressure ultra pure water rinsing (100 bars) – refurbishment in progress



Available infrastructure (2)



- **Building SM18:**

- Cavity/cryomodule assembly
- Two 15m clean rooms (class1000/10) + access zone
- One 4 meter high clean room (class100)
- Four vertical cryostats
- Two bunkers
- High RF power zone
- Main control room
- Cryogenic system
 - Limited availability (LHe to be shared with other SM18 activities -> LHC magnets)
 - LHe distribution line will be replaced in 2011


SPL cryomodule – Cavities, Assembly

- Will profit from all existing infrastructure (W.W 's talk)
 - Clean rooms
 - UP water rinsing stations
 - EP station
- SM18 clean rooms not fully compliant with SPL cryomodule assembly requirements
 - Must be equipped with:
 - Dressing zone (class100)
 - UP water rinsing zone(class 100) – main couplers, hom couplers,..
 - Existing 15 m class 10 room shall be equipped with vacuum leak detection equipment

→ feasibility study to be made!!


SPL cryomodule – Cavity tests

- SM 18 is equipped with four vertical cryostats
 - LHC cavities (4.2K) – operational
 - HIE Isolde cavities (4.2K) – availability: Summer 2010
 - Nb surface studies / diagnostic tools developments (2K) – operational
 - SPL cavities (2K) – availability: end 2010
- One fellow will be working on SC cavities diagnostic tools
 - Temperature mapping
 - LHe second sound





SPL – high power tests (1)

- Two bunkers in SM18:
 - Bunker A :
 - will be modified for 2K operation (2011) /control system to be completely renewed
 - will be modified for the Linac4 RF structure tests (2011 -> end 2012)
 - ready for SPL cryomodule tests in 2013
 - Bunker B:
 - operational
 - priority: LHC cryomodules
 - HIE Isolde cryomodule tests (2012/14)



SPL – high power tests (2)

- Bottleneck is the High RF power zone:
 - Very crowded area:
 - 100kV, 40A PC
 - LHC high RF power
 - LHC HV bunker
 - 352MHz 1.3MW klystron (Linac4 tests)
 - No real extension possible
- Upgrade towards L4 / SPL tests:
 - Move LHC HV bunker to free space for pulsed modulator
 - 2011: installation of a 2Hz Linac 4 type modulator
 - Asap: integration of 50Hz modulator – **footprint??**
 -> **being studied...**
 - Specify & order high power components
 - 704MHz, 1MW klystron (specs 90% completed)
 - **Interface with modulator not defined!**
 - Circulator & RF load (specs to be done)
 - WG components (specs to be done)
 - Specify & built control system
 - ready early 2011 for L4 tests



SPL – high power planning

	2010			2011				2012				2013
	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1
SM18 - 2K Vertical Cryostat		operational			new LHe line							
SM18 - 2K Bunker						new control system			New LHe line			
704MHz RF power		specs ready			orders					installation		
50Hz modulator			Footprint/dim							installation		
High power test place (352-704)		Integration/prep for L4								SPL modif		
Clean rooms upgrade			study?			upgrade?						

LHC OPERATION	LHC SHUTDOWN / STARTUP
LINAC 4 EQUIPMENT TESTS	
	LINAC4 INSTALLATION
HIE ISOLDE CAVITIES & CRYOMODULES	

Conclusions

- Several projects going on in parallel
 - Existing infrastructure: good starting point
 - Objective is to get the best share of the existing infrastructures between activities/projects
- Upgrade of infrastructures is ongoing, in particular for the SPL cryomodule
 - High pressure UP water rinsing
 - Electro-polishing station (new)
 - Cavity vertical test stations, diagnostic tools
 - SM18 LHe distribution line
 - Clean room upgrade necessary – possible???
- SPL cryomodule high power tests
 - Bunker A in SM18 requires hardware modification to host SPL high power tests
 - 50Hz modulator size?
 - Will profit from preparation work done for L4
 - Specification documents for 704MHz high power equipment in preparation