

Status of SC cavity development (SPL WG2 report)

W. Weingarten

Outline of talk 1/2

- ▶ Participants to cavity WG activity
- ▶ Cavity geometry

[Fabrication of Nb and Cu SPL cavities and required tools](#) , [Towards the final design of the beta=1 cavity](#), [Towards Common Interfaces](#), [RF parameters for the BNL and CEA cavities](#), [\$\beta=1\$ cavity-parameters](#), [Discussion on the RF parameters for the SPL cavities - CEA vs. BNL II](#), [beta = 0.65 design features](#), [SCRF Research at JAI@RHUL - intra-cavity coupling in short cryomodule](#)

- ▶ Mechanical and material issues [spec's Nb sheets](#) , [Towards the acquisition of niobium: mechanical calculations](#)

- ▶ Power coupler (cf. also Ed Ciapala's presentation)

- ▶ HOM issues

[SPL - HOM Qload - coupled S-parameter calculations](#), [Beam tube damping estimationsfor SPL cavity](#), [Beam tube damping estimations for SPL cavity, cont'd](#) , [Longitudinal HOM power estimationsfor pulsed beams](#), [Damping Considerations for coax type couplers](#) , [Qext-limits](#), [transition section and damping](#)

- ▶ Magnetic shielding

- ▶ Update parameter list [SPLparameterList](#)

- ▶ Electropolishing (EP) status at CERN

- ▶ (Safety issues [CERN safety requirments for pressure vessels](#))

- ▶ Concluding remark

Outline of talk 2/2

references

Presented material is based on the following sources:

Meetings related to cavity activity since last (3rd) collaboration meeting on 11 -13 Nov. 2009:

- ▶ 5 cavity WG meetings

<http://indico.cern.ch/categoryDisplay.py?categId=2722>

- ▶ 21 Jan 2010, RF needs for SPL SC cavity tests

<http://indico.cern.ch/conferenceTimeTable.py?confId=80891#20100121>

- ▶ 16 - 17 March 2010, Review of SPL RF power couplers

<http://indico.cern.ch/conferenceTimeTable.py?confId=86123#20100317>

- ▶ 1st Annual RFTech meeting

<https://indico.desy.de/getFile.py/access?contribId=7&sessionId=1&resId=0&materialId=slides&confId=2831>

Participants to cavity WG activity

- ▶ **CERN, Geneva,**
 - ▶ BE-RF (clean room assembly, low and high power RF tests, inspection, RF power coupler)
 - ▶ TE-CRG (cryogenics SM18)
 - ▶ TE-VSC (surface preparation: chemical and electro-polishing, high pressure water rinsing)
 - ▶ EN-MME (manufacture of $\beta = 1$ cavities and He tank)
- ▶ **CEA - Saclay, France** (design and fabrication of $\beta = 1$ cavity, 5 helium vessels, 9 tuners, test bench availability 8 RF power couplers)
- ▶ **CNRS - IPN Orsay, France** (design, fabrication and test of $\beta = 0.65$ cavity equipped with a titanium helium reservoir)
- ▶ **TEMF University of Darmstadt, Germany** (el-mag. simulations: interaction of power coupler with beam)
- ▶ **University of Rostock, Germany** (el-mag. simulations of HOM antenna coupler design)
- ▶ **BNL, Upton N.Y., USA** (manufacture of $\beta = 1$ cavity)
- ▶ **TRIUMF, Vancouver, Canada** (manufacture of $\beta = 1$ cavity)
- ▶ **Royal Holloway, University of London, John Adams Institute for Accelerator Science, U.K.** (room temperature RF measurements on cavity models)

Cavity geometry 1/5 design considerations

- ▶ Maximum allowed pressure for cavity beta =1 and beta =0.65 design

Max pressure at 300 K : 1.5 bars

Max pressure at 2K: 2 bars


- ▶ Beta=1 cavity

Position of HOM ports

- ▶ opposite to power coupler (ease of manufacture)
- ▶ Vertical upwards for possible future cooling considerations => the Power coupler will be downwards
- ▶ The other HOM port will be positioned at 60 deg / vertical
- ▶ The pick-up port downwards

- ▶ Beta=0.65 cavity

- ▶ same end cavities as for beta=1 and to modify the inner design




Saclay designed $\beta = 1$ cavity geometry is the reference

Cavity geometry 2/5

phase relation between string of several cavities (π - mode)


present layout with inter-cavity bellows of 100 mm length

$$2.05 \cdot \lambda/2$$



proposed new layout with inter-cavity bellows of 89.4 mm length

$$2 \cdot \lambda/2$$



RF power coupler
phase = -180°




RF power coupler
reference phase = 0°



RF power coupler
phase = 180°

Cavity geometry 3/5





Geometry of He tank, magnetic shielding and position of power coupler flanges still to be finalized

Cavity geometry 4/5

inter-cavity coupling in string of 4 cavities




Eigenmodes exist in **all** cavities



Cavity geometry 5/5

study of multipacting in end groups

MULTIPACTING BNL & CEA END GROUPS




Number of secondary electrons surviving after 20 impacts normalized to the secondary yield of Nb

$\beta = 1$ cavity buckling calculations


Cavity with **2.5 mm thickness** (worst case); boundary conditions fixed-fixed (best case); external pressure loading:

1st buckling mode (security factor of 14 with respect to the p=2bars loading)




Power coupler 1/2


three possible remaining designs



SPL-CEA HIPPI coaxial disk water cooled window



SPL-SPS coaxial disk air cooled window



SPL-LHC cylindrical air cooled window

All use the same double walled tube

All use the same vacuum gauge, electron monitor and arc detector

We have designed them to be compatible without modifying the cryomodule

Power coupler 2/2

Decisions after March 2010 Coupler Review



- ▶ A single window coupler
- ▶ A fixed coupler
($Q_{\text{ext}} = 1.25 \times 10^6$)
- ▶ With a Double Walled Tube
- ▶ Mounted in clean room with its double walled tube horizontally in only one operation
- ▶ With its final position vertically below the cavity (regarding HOM, cryo-module integration, pollution, etc... requirements)
- ▶ With a HV DC biasing capacitor
- ▶ Air cooled

HOM issues 1/6


do we have the optimum design of cavity and end groups?

FUNDAMENTAL MODE

Parameter	BNL II	CEA	% Diff
Frequency	704	704	
Epk/Ea	2.18	2.04	-6.4 %
Bpk/Ea	4.48	4.30	-4.0%
R/Q	504	555	+9.2%
Kcc	3 %	-	



R/Q DIPOLE MODES




what Q do we need wrt beam break up simulations under various conditions for whole linac?

Q_{ex} limits based on beam dynamic simulations

Simulated cases: **nominal**, RF errors, chopped beams, fundamental pass-band modes

Example: nominal



- one HOM with max R/Q in each cavity present.

Overall conclusion:


To be on the save side and keep all operation options open a $Q_{ex} = 10^5$ is recommended!

HOM issues 3/6


what is the longitudinal HOM power for pulsed beams to be dumped into the HOM load/cavity?

f (HOM) precisely on beam spectral line $I = 40$ mA; pulse length 1 ms, $R/Q = 100 \Omega$; rep. rate 50 Hz; $f_{HOM} = 2.1$ GHz; $Q_0 = 10^{10}$

radiated power to HOM load



dissipated power in cavity



The main beam Fourier components (n-352 MHz) contribute significantly to the HOM power, the 50 Hz Fourier component, however, only marginally; to reduce the HOM power below 100 W, the Q-value of the HOM must be $Q < 10^4$




HOM issues 4/6

what is the longitudinal HOM power for pulsed beams to be dumped into the HOM load/cavity?


f (HOM) off beam spectral line

$I = 40 \text{ mA}$; pulse length 1 ms, $R/Q = 100 \ \Omega$;
rep. rate 50 Hz; $f_{\text{HOM}} = 2.1 \text{ GHz}$; $Q_0 = 10^{10}$

radiated power to HOM load



dissipated power in cavity




Avoiding the main beam Fourier components by the HOM frequencies within 10 kHz reduces the HOM power significantly, with a tendency to become even smaller for larger Q-values ($P < 1 \text{ W} @ Q > 10^7$)

(this statement is presently under debate for a beam with charge jitter)

is sufficient damping by coaxial antenna possible?

H.-W. Glock; ; K. Rothemund;
U. van Rienen. CSC – A
System for Coupled S-
Parameter Calculations,
TESLA-Report 2001-25

Q-value spectrum for 0 mm antenna depth:



by far to heavy loading of fundamental mode => ...

... the main message remains:


Pick-ups without fundamental mode filters will not be able both to preserve fundamental mode Q and damp all HOMs sufficiently.

Confirmed by Wolfgang Weingarten's 2D computations using beam pipe dampers.



HOM issues 6/6

do stainless steel bellows provide sufficient damping?




Ratio of Q-values between making the bellows superconducting and made out of stainless steel.



Magnetic shielding 1/2

Clamp to range: (Min: 0/ Max: 5e-006)



d=3mm

$$\mu_r = 42000$$

Type: B-Field
 Component: Abs
 Plane at x: 0
 Maximum-2D: 0.0253542 Us/m^2 at -1.41208e-014 / -243 / 731.224



- $\mu_r = 42.000$ needed for the whole temperature range for 3 mm sheet
- End caps are necessary
- A gap of a few millimeters between end caps and cylinder can be tolerated
- Holes lead to higher field values than $1\mu\text{T}$ in spots of approximately their size

My recommendations:

- External Shield of Cryoperm (3 mm)
- As close as possible to the helium tank
- Annealing of tubes and end caps


Tobias.Junginger@quasar-group.org

Update Parameter list 1/2

what Q-value may we expect?

Plot was obtained by a fit from “world” data @ 600 MHz < f < 800 MHz

Based on paper: <http://accelconf.web.cern.ch/AccelConf/srf2009/papers/tuppo052.pdf>



Cryo design parameters (assuming 40 mA/0.4 ms beam pulse as nominal, 20 mA/0.8 ms beam pulse as ultimate)

<u>Parameter</u>	<u>Unit</u>	<u>low-beta</u>	<u>high-beta</u>
		nominal/ultimate	
Cavity bath temperature	[K]	2.0	2.0
Beam loss	[W/m]	1.0	1.0
Static loss along cryo-modules at 2 K	[W/m]	?	?
Static loss at 5-280 K	[W/m]	?	?
Accelerating gradient	[MV/m]	19.3	25
Quality factor Q	[10⁹]	6/3	10/5
R/Q value	[Ω]	290	570
Cryogenic duty cycle	[%]	4.09/8.17	4.11/8.22
Coupler loss at 2.0 K	[W]	<0.2/0.2	<0.2/0.2
HOM loss at 2.0 K in cavity	[W]	<1/<3	<1/<3
HOM coupler loss at 2.0 K (per coupler)	[W]	<0.2 /0.2	<0.2/0.2
HOM & Coupler loss 5-280 K	[g/s]	0.05	0.05
Tunnel slope	[%]	1.7%	1.7%
Magnet operating temperature	[K]	ambient	ambient
No. of cavities		60	200
No. of cryostats		20	25
Cavities per cryostat		3	4/8
Dynamic heat load p. cavity	[W]	4.2/13.4	5.1/16.2

Updated values in red



EP status at CERN 1/3 pipework and acid tank

Leonel Marques Antunes Ferreira
Sergio Calatroni/CERN-TE-VSC



Ready to be installed in the safety cabinet foreseen for the treatment

EP status at CERN 2/3 walk-in booth

Leonel Marques Antunes Ferreira
Sergio Calatroni/CERN-TE-VSC



Separated environment with
dedicated air washer for
safety



All cabling and services
connections have been
performed



EP status at CERN 3/3 tentative planning

Leonel Marques Antunes Ferreira
Sergio Calatroni/CERN-TE-VSC

- ▶ Setup completed by mid-2010 (major hardware, excluding EP cathode)
- ▶ Simulation work of EP process is ongoing (with the Elsyca¹ software)
- ▶ A cathode suitable for EP of $\beta = 1$ cavities should be designed and manufactured by end-2010

¹Simulation software for calculation and optimisation of potential, current density, deposit thickness distributions in electrochemical reactors

Concluding remarks 1/2

- ▶ The reference **mechanical design** of cavity + He-tank + magn. shielding tank is mainly based on the Saclay work
 - ▶ some minor features of the He tank and related integration issues for the tuner and power coupler still to be finalized¹ as well as the integration of the magn. shielding;
 - ▶ the Nb sheets specification is defined (call for tender in preparation)
- ▶ The **power coupler** will be a coaxial 50 Ω line of single window type and a double wall gHe cooled outer conductor and air-cooled inner conductor;
 - ▶ distance of flange to beam axis to be defined¹
- ▶ **Beam breakup studies** stipulate the HOMs to be damped to an equivalent $Q < 10^5$

¹ preparatory meeting foreseen on Thursday 1st July, 16h00, meeting room SAM-ASK lower floor of Grand Hotel

Concluding remarks 2/2

- ▶ Pros and cons of alternate designs of the end group with regard to the deposited **HOM power** were discussed; no follow up possible (by now) due to time constraints
 - ▶ At the recommended $Q = 10^5$, the beam deposited power into the HOMs can achieve ~ 1 kW
 - ▶ Cures to reduce the beam deposited power consist in
 - ▶ avoiding the beam Fourier components by at least 10 kHz with a Q-value $Q > 10^7$ or
 - ▶ damping the HOMs to below $Q = 10^4$
 - ▶ The previous idea (HOM workshop) of damping the HOMs by a normal conducting (nc) beam tubes and additional coaxial antennas (without filter) does not survive; however, damping by nc beam tubes turns out to be efficient above 1800 MHz (the damping action of the power coupler not yet included!)
 - ▶ Hence if we want to damp the HOMs equivalently to a Q-value of 10^5 or even more, we should envisage notch filter type HOM couplers
- ▶ A reference design of the **magnetic shielding** exists
- ▶ The **cavity** and **cryogenic parameter** list was updated
- ▶ The build-up of the CERN **EP installation** is progressing