

J-PARC Linac: Status and Upgrade

Kazuo Hasegawa
Japan Atomic Energy Agency

4th SPL Collaboration Meeting jointly with ESS
Lund, June 30 -July 02 2010

Outline

-J-PARC facilities

-Linac

Parameters

Status of components


-Availability of J-PARC Accelerator

-Upgrade of the linac

Energy upgrade

Beam current upgrade

J-PARC Facility Layout at Tokai, JAEA Site



**Materials and Life Science
Experimental Facility (MLF)**

**Hadron Experimental
Facility**

**3-GeV Rapid-Cycling
Synchrotron (RCS)
(Circumference 350m)**

**ADS: Accelerator Driven
Nuclear Waste
Transmutation System
(in the 2nd phase)**

**Linac (181 -> 400MeV)
(330m)**

**Neutrino Experimental
Facility**

**Main Ring Synchrotron (30-50 GeV)
(Circumference 1600m)**


Photo in Feb. 2006

***Multi-Purpose
Facility***

Joint Project between KEK and JAEA

Location of J-PARC at Tokai





Linac (330m)



3 GeV Synchrotron (350m)




Main Ring Synchrotron (1600 m)



**Superconducting magnets for
the neutrino beamline**

J-PARC Construction Schedule

Feb. 27 2006



Construction Start

Time when this schedule was created (J-PARC Center started)

Start of n & μ User Programs


Now

Linac Parameters




Major Parameters

- Particles: H^- (negative hydrogen)
- Energy: 181 MeV, The last two SDTLs are used as debunchers. (400 MeV for ACS, 600 MeV for SCL)
- Peak current: 30 mA (50 mA for 1MW at 3GeV- \rightarrow Ion source, RFQ)
- Repetition: 25 Hz (additional 25 Hz for ADS application)
- Pulse width: 0.5 msec




Ion Source




J-PARC Ion source

- * Plasma chamber :
100mm diam. 120mm length
- * Plasma production :
Arc discharge (LaB6 filament)
- * Number of filament : 1
- * Cesium : free
- * Beam aperture : 9mm diam.
- * Number of electrode : 3
- * electron suppression :
magnets in extraction electrode




Photograph of LaB6 filament

Front End





Ion source and LEFT



Ion source and RFQ

The ion source is in the insulator to take minimum length to the RFQ


Ion source performance: beam current



Beam current: 36 mA



Pulse length: 500μs

Repetition: 25 Hz




The ion source meets the specification of the 1st stage of the J-PARC.

Medium Energy Beam Transport




Inside of the chopper cavity
324 MHz, Mode TE₁₁, QL~11
Rise and Fall times: 15 nsec



Chopper tuning



Measured residual current with a wire scanner

Peak current: 25 mA



Phase optimization


100-shot average




DTL/SDTL

Main Parameters


| | DTL | SDTL | |
|------------------------|---------|----------|------|
| Energy | 3-50 | 50-190.8 | MeV |
| Frequency | 324 | 324 | MHz |
| Section Length | 27.1 | 91.2 | m |
| Accelerating Field, E0 | 2.5-2.9 | 2.5-3.7 | MV/m |
| Number of Cavities | 3 | 32 | |



Compact electro-quadrupole magnets are accommodated as tuning knobs.



DTL




SDTL

Linac RF System

- Operation frequency: 324 MHz
- Total 20 klystrons (max.3 MW), 6 DCPS (#1~6)
- RF flat top: 600 μ s (25Hz)
- Requirements of cavity field stability
< +/-1% (amplitude), < +/-1deg (phase)




Klystron Gallery



RF System: Klystron


- 20-unit of klystrons have been operated for **16,400 hours**. (from 2006 Oct. to 2010 June)
- There are **no serious troubles**, such as a discharge in e-gun, vacuum degradation, arcing in output window.



| | |
|-------------------|-------------------------|
| Peak Power | 2.5 (max. 3.0) MW |
| Pulse Width | 650 μ s |
| Repetition | 50 Hz (25 Hz) |
| μ -Perveance | 1.37 A/V ^{3/2} |
| Gain | 50 dB |
| Efficiency | 55 % |
| Beam Voltage | 105 (max. 110) kV |
| Beam Current | 45 (max. 50) A |
| Mounting Position | Horizontal |
| No of Klystron | 23 = 20 + 3 (spare) |

324MHz Klystron (E3740A)


Low Level RF System



Digital FB&FF Control for Stabilization of Cavity Field
One klystron powers 2 cavities (SDTL section)
The FB system controls the vector sum of the 2 cavity fields.


Performance of the FB Control

Cavity field stabilization (600- μ s RF pulse)



No Feedback Control

10% in amplitude and 25 degrees in phase sages are due to the Klystron DC voltage sag of about 3.4%



With Feedback Control (Gain: P=5, I=5/1000)

Amplitude and phase are stabilized to be $\pm 0.15\%$ and ± 0.15 degrees, respectively. These ripples at the transient have been compensated with FF system.

Performance recovery of the RFQ




Since the autumn of 2008, the most urgent issue of the linac was discharge in the RFQ. The RCS beam power for users was limited at 20 kW due to the RFQ problem.

In the 2009 summer shutdown,
improved vacuum system
performed in-situ baking



Hydro-carbon components in residual gases gradually reduce during rf conditioning

Performance of the RFQ was recovered.




- ① REDUCE GAS FLOW FROM UPPER STREAM.
- ② ADOPT MOISTURE FREE FILTER.
- ③ OIL FREE ROUGH PUMP SYSTEM.

RFQ PUMP SPEED [l/sec]: 3,300 ➤ 12,500

ION SOURCE PUMP SPEED [l/sec]: 6,000 ➤ 9,000

History of beam delivery to the MLF







After the recovery of Linac-RFQ, high power operation of the RCS has become possible and 120 kW operation has started for the MLF users.

Neutron beamline : 12 beamlines are now under commissioning and open for users.

Muon beamline: The highest intensity beamline in the world with the 120 kW beam.

Availability of the Accelerator




Energy upgrade of the Linac




We have successfully marked the milestones of the J-PARC.


- ❑ The full potential of the J-PARC complex cannot be realized with a 181 MeV linac. (e.g. 1MW@RCS, 0.75MW@MR)
- ❑ The construction of 200 to 400MeV part of the linac was funded through the supplementary budget of JFY2008.



Annular Coupled Structure (ACS) for High-Energy Structure




a) Disc-loaded




d) SCS (Knapp, LANL)




b) APS-I (T. Nishikawa, KEK)




e) ACS (Kageyama, Yamazaki, KEK)



c) APS-II



f) DAW (Andreev, Moscow)



Coupling slot


Cooling channel

Vacuum port

Half-cell piece

| | | |
|-------------------|-----------|--------------|
| Energy | 190.8-400 | MeV |
| Frequency | 972 | MHz |
| Section Length | 108.3 | m |
| E0 | 4.1 | MV/m |
| RF pulse width | 0.6 | ms |
| Duty factor | 3 | % max |
| Number of modules | 21 | Acceleration |
| | 2 | Bunchers |
| | 2 | Debunchers |

Machining of ACS disks



Brazing and Assembling of ACS




Vacuum furnace



Assembling

ACS Structure



The lowest energy ACS module
The ACS cavities are preparing for
mass production at factories.




ACSs will be installed
in the tunnel in 2012,
where currently using
as a beam transport
line.

972MHz Klystrons

| | |
|--------------------|---------------------|
| Cathode voltage | 106kV (110kV) |
| Cathode Current | 45A (50A) |
| Saturated RF power | 3.1MW (3MW) |
| Gain | 51dB (>50dB) |
| Efficiency | >60% (>55%) |
| Band width | ± 5 MHz (>5MHz) |
| | (Specifications) |



Three tubes of klystrons.



Input-Output characteristics.

Installation at the Gallery



Klystron stations under construction.



Waveguides were installed from the klystron gallery to the accelerator tunnel during the summer shutdown in 2009.



Ion Source Towards 1MW Goal



We have been operated at 30 mA without Cs routinely. But we need 50 mA for 1MW goal.

We decided Cs-seeded source driven with RF is the first candidate for 1MW source.
->An RF source is superior to filament one for reduction of the amount of Cs.

Jan- 2010: Start of preparatory-experiment with existing RF ion source



Photograph of RF pre-experiment set up

Mar- 2010: Visit SNS to study RF ion source technology

*SNS RF source has good performance.


R&D of an RF ion source is underway.

RFQ-#1, #2 and #3

The performance of the present RFQ (#1) is getting better, we continue to make a back up RFQ (#2) and designing a final (#3) RFQ.



The #2 RFQ is a demonstration of #3 structure.

| | #1(present) | #2 (backup) | #3(final goal) |
|--------------|--------------------------|--------------------------------------|----------------|
| Peak current | 30mA | 30mA Beam dynamics follows the #1 | 50mA |
| Structure | RF-Vacuum dual structure | One structure | One structure |



View of #1 RFQ and cross section Image of #2 and #3

RFQ-#2



Vane modulation is produced by an NC ball-end mill.



Set up before brazing


Superconducting Proton Linac

History of SCL at J-PARC(JAERI)

- 1995 R&D of the SCL started
- 2000 Test of 600 MHz cryomodule, $\beta=0.886$, 5 cells
- 2002 Design of 972 MHz cryomodule
- 2002-2009 Test of 972 MHz cryomodule

Design Parameters



| | |
|--------------------|---------------------|
| Energy | 400-600 MeV |
| Frequency | 972 MHz |
| β | 0.71-0.79 |
| No. of Cell | 9 cell/cavity |
| No. of Cavity | 2 cavity/cryomodule |
| No. of Cryomodule | 11 cryomodules |
| Length | 57.7 m |
| Surface Peak Field | 30 MV/m |
| Accelerating Field | 9.7-11.1MV/m |



Superconducting Proton Linac

Cryomodule design

- Two 9-cell elliptical cavities at 2K (972 MHz)
- Stiff structure for cavity and tuner to reduce Lorentz force detuning
- 80K thermal shield by LN₂ and 5K thermal intercept by LHe



SC Linac Experimental Results





◆ RF Properties

Surface peak Field (E_{sp})
37, 35 MV/m (Target 30MV/m)
at duty factor of 3%

◆ Cryogenic Properties

Heat leak : 10W (Design 5W)



- At the first test, higher duty factor operation is limited up to 3% due to poor cryogenic performance. Improvement of the cryogenic performance was done in 2007.
- Vector sum test was well performed in 2009.
- The RF power supply is moved to the J-PARC linac building for the energy upgrade (reuse to reduce cost). No activity since then, but still in the Phase-2 upgrade plan.

■ Commissioning and operation of the J-PARC linac is progressing well.

- The RFQ discharge problem has been almost resolved. Beam delivery to MLF(120kW), Neutrino (50-100kW), and Hadron users.
- Beam availability of the accelerator is more than 90%.

■ Performance upgrade

- The 200-400 MeV linac part was funded and construction is underway.
- The 2nd RFQ is under construction as a backup and R&D of the next high current RFQ.
- The R&D of RF ion source for higher beam current has been started.
- Superconducting linac is still in the second phase of the project.

End of the talk